SD Geotesting Solutions and Consultant Pvt. Ltd.

Lab Address - Near Junona Road, Babupeth, Chandrapur, Maharashtra - 442403
7767900097, 7721900090 info@sdgeosolutions.in

Head Office : Plot No. F - 43, National Highway NH06, Near Hyundai Service, MIDC, Amravati, Maharashtra - 444607
7020134781, 7767900082 sd.geosolutions@gmail.com

Test Report for Water

T.R.No: SD-CHD/150426-3/R-001

Date:17/04/2026

***To,**
Sharon Public School
Shengaon, Behind Kabir Petrol Pump,
Ghugus, Maharashtra 442505.

***Name of Client**	:-	Sharon Public School
***Contact Person Name**	:-	Manish S. Mishra
***Contact Person Number**	:-	9860487443
***Subject**	:-	Test Result Of Water Sample.
***Your Ref.**	:-	TRQ Dated :- 15/04/2026
***Location**	:-	At. Ghugus

Dear Sir,
With subject and reference cited above, the test result report is as follows,

PARTICULAR OF SAMPLE (S)

Discipline	:-	Chemical Testing			
Material Group	:-	Drinking Water	**Sample ID**	:-	CHD/150426-3/S-001
Nature	:-	Tap Water	**Temperature**	:-	25.2°C
Sample No. Details	:-	One Sample	**Humidity**	:-	48%
Quantity	:-	1 Liter	**Test Location**	:-	In Lab
Packing/Container	:-	Plastic Bottle	**Test Start Date**	:-	15/04/2026
Date of Receipt	:-	15/04/2026	**Test End Date**	:-	17/04/2026

Lab Job No. :- CHD/150426-3/J-001		**TEST RESULT**				
Sr. No.	**Name of Test**	**Test Method**	**Result**	**Requirement (Acceptable Limit) as per IS 10500 : 2012 RA:2018**	**Permissible Limit in Absence of Alternate Source as per IS 10500 : 2012 RA:2018**	**Unit**
A. Organoleptic & physical Parameter						
1	Colour	IS 3025 Part - 04	**0.20**	5 Max.	15 Max.	CU
2	Odour	IS 3025 Part - 05	**Agreeable**	Agreeable	Agreeable	---
3	Teste	IS 3025 Part - 07 & 08	**Agreeable**	Agreeable	Agreeable	---
4	pH Value @ 25.0 °C	IS 3025 Part - 11	**8.13**	6.5 to 8.5	No Relaxation	---
5	Electrical Conductivity	IS 3025 Part - 14	**328**	---	---	µs/cm
6	Total Dissolved Solid (TDS)	IS 3025 Part - 16	**170**	500 Max.	2000 Max.	mg/l
B. General Chemical Parameters						
7	Magnesium (as Mg)	IS 3025 Part - 46	**14.52**	30 Max.	100 Max.	mg/l
8	Total Hardness (as $CaCO_3$)	IS 3025 Part - 21	**81.70**	200 Max.	600 Max.	mg/l
9	Total Alkalinity (as $CaCO_3$)	IS 3025 Part - 22	**67.80**	200 Max.	600 Max.	mg/l
10	Calcium (as Ca)	IS 3025 Part - 40	**43.45**	75 Max.	200 Max.	mg/l

Prepared By
Premsingh Thakur

Verified By
Premsingh Thakur
Chemical Testing Incharge

Authorized Signature
Sagar Bhengle
CEO/Technical Manager

SD Geotesting Solutions & Consultant Pvt. Ltd.

Note:-
1. Samples not drawn by us, unless otherwise mentioned. 2. Samples may be destroyed / removed away from Laboratory after Testing, unless otherwise particular request is made 3. This report in full or part may not be reproduced, published or used for any legal action unless prior permission is secured from M.D SDGSCPL Chandrapur. Subject to Chandrapur Jurisdiction. 4. Although Site name has been mentioned, SDGSCPL is not be responsible for the actual site conditions. 5.The star * marked in the report represent the information furnished by the agency. 6. This report pertains only to sample (s) submitted by the client and tested by lab.

--End of Report--